

November 21, 2011

PVDR 1101.00

Mr. Doug Buch PaveDrain, LCC 4880 W. Abbott Avenue Greenfield, WI 53220

RE: PAVEDRAIN CONCRETE BLOCK

STRUCTURAL ANALYSIS FOR AASHTO TRUCK LOADING

Dear Mr. Buch:

We have completed our structural analysis of the PaveDrain concrete blocks and find them capable of supporting AASHTO HS-20 and H-20 truck loading.

We analyzed the the blocks as unreinforced concrete arches supporting a uniform truck tire load with impact per AASHTO standards. The arches were reviewed considering both a fixed end condition and a pinned end condition. We used the ASTM D 6684-04 specified minimum compressive strength of 4000 psi for the concrete. The actual tested strength of the PaveDrain units averages 8900 psi which is more than double the strength used in our structural calculations.

As with all vehicular traffic paving systems, the subgrade soil and base preparation for the PaveDrain blocks must be properly prepared and is critical to the performance of the system.

Sincerely,

PENNONI ASSOCIATES INC.

Germaine E. Lenz, PE, SECB Structural Project Engineer

GEL/gel

Attachment: Calculations (4 pages)

cc: Khaled Hassan, Pennoni

Charlie Snyder, Pennoni

L:\Projects\PVDR\PVDR1101-Pave Drain H-20 Review\PaveDrain letter 2011-11-21.docx





Project No.: PVDR-1101

Report Date: October 11, 2011

Client: Mr. Doug Buch

Address: PaveDrain, LLC

4880 W. Abbott Avenue Greenfield, WI 53220

Project Name: PaveDrain Inc. Lab Tests

Date Received: September 26, 2011

Laboratory Number:10- 95209

Date of Compression Testing: October 4, 2011

Unit Specification: ASTM D6684

Unit Designation and Description: Dry-Cast Articulating Concrete Block

5.65" Block

## **Summary of Test Results**

Physical Property	Specification Values	Average Test Results		Physical Property	Specification Values	Average Test Results	
Net Compressive Strength	≥ 4000	9030	psi	Min. Faceshell Thickness (FST)		-	in.
Gross Compressive Strength		8910	psi	Min. Web Thickness (WT)		-	in.
Density	<u>≥</u> 130	141.2	pcf	Equivalent Web Thickness		-	in.
Absorption	0-9.1	6.3	pcf	Equivalent Thickness		-	in.
Percent Solid		98.8	%	Net Cross-Sectional Area		16.05	in. <sup>2</sup>
Moisture Content		N/A	%	Gross Cross-Sectional Area		16.27	in. <sup>2</sup>

## Individual Unit Test Results

Compression Units

Specimen No.	Received Wt,	Cross-S	ectional Area	Max. Load	Compressive Strength		
	W <sub>R</sub>	Gross	Net	IVIAX. LUAU	Gross	Net	
	lb.	in. <sup>2</sup>	in. <sup>2</sup>	lb	psi	psi	
1	0.00	16.25	16.05	141800	8720	8830	
2	0.00	16.32	16.09	141755	8680	8810	
3	0.00	16.24	16.01	151770	9340	9470	
Average	0.00	16.27	16.05	145108	8910	9030	

<sup>\*</sup> Net area determined from absorption specimens unless solid units are used.

Absorption Units

Specimen No.	Average Width	Average Height	Average Length	Average Min. FST	Average Min. WT
NO.	in.	in.	in.	in.	in.
4	2.0	4.2	8.2	-	
5	2.0	4.2	8.2	-	-
6	2.0	4.2	8.2		-
Average	2.0	4.2	8.2	-	-

Specimen No.	Received Wt, W <sub>R</sub> **	Immersed Wt,W <sub>i</sub>	Saturated Wt, W <sub>S</sub>	Oven-Dry Wt, W <sub>D</sub>	Absorption	Density	Net Volume	Net Area	Percent Solid	Moisture Content** % of total
	Ιb	lb	lb	lb	pcf	pcf	ft <sup>3</sup>	in <sup>2</sup>	%	absorption
4	0.00	3.36	5.82	5.57	6.3	141.3	0.0394	16.15	98.8	N/A
5	0.00	3.31	5.72	5.48	6.2	141.9	0.0386	16.17	97.8	N/A
6	0.00	3.33	5.79	5.54	6.3	140.5	0.0394	16.15	99.9	N/A
Average	0.00	3.33	5.78	5.53	6.3	141.2	0.0391	16.15	98.8	N/A

<sup>\*\*</sup>Received weight determined at the time of unit delivery to the job site or from units sampled at that time and delivered to the laboratory in sealed containers for moisture content determination.

Remarks: The units were tested according to ASTM C140. This set meets the requirements of ASTM D6684.

These units are capable of supporting AASHTO HS-20 and H-20 loading with proper subgrade and base installation.

Chas M. Snyder, P.E Laboratory Manager

Quinton D. Davis, Jr. Division Manager

